

GEODETSKI ELEMENTI TRASE PRISTUPNOG PUTA I CRPNE STANICE DOLAC NA LAŠVI

 EU funded project Projekat finansira Europska Unija		 WYG International part of the WYG group creative minds safe hands	
Client/Klient		Consultant/Konsultant	
INFRASTRUCTURE PROJECTS FACILITY IN THE WESTERN BALKANS		WYG INTERNATIONAL UK	 INSTITUT ZA HIDROTEHNIKU GRADEVINSKOG FAKULTETA U SARAJEVU
Project/Projekat			
REGIONALNI SISTEM VODOSNABDIJEVANJA PLAVA VODA			
Project status/Tip Projekta	Drawing date /Datum crteža: 09.08.2011. Drawing approved/Crtež odobren: 21.09.2011.	Drawing status /Status Crteža FINAL	Drawing scale/Mjerilo crteža (Priloga)
GLAVNI PROJEKT			Format A3(420/297 mm)
Drawing name/Ime Priloga	Prepared by:		Drawing no/ Prilog broj
GEODETSKI ELEMENTI TRASE PRISTUPNOG PUTA I CRPNE STANICE DOLAC NA LAŠVI	 INSTITUT ZA HIDROTEHNIKU GRADEVINSKOG FAKULTETA U SARAJEVU Stjepana Tomića 1, Sarajevo, Bosna i Hercegovina Tel./Fax: 21 24 66/67; 20 44 95; FB: 405; E-mail: hies@hies.com.ba ID broj: 4200689/1003, PDV broj: 250009/1003, Broj upisa u sudski registar: 10/111063		4.8
			Sheet/List
			Of/Od
			1 1

GEODETSKI ELEMENTI TRASE

PRISTUPNI PUT DO CS DOLAC NA LAŠVI

	Koordinata		
TAČKA	Y	X	Komentar
1	6 474 978.50	4 897 980.81	Početak pristupnog puta
2	6 474 984.35	4 897 969.82	
3	6 474 987.21	4 897 965.58	
4	6 474 992.34	4 897 959.69	
5	6 474 993.20	4 897 958.94	
6	6 474 999.55	4 897 953.88	
7	6 475 004.26	4 897 950.93	
8	6 475 009.24	4 897 948.53	
9	6 475 012.80	4 897 946.13	
10	6 475 011.04	4 897 934.91	
11	6 475 000.92	4 897 936.97	
12	6 475 000.14	4 897 937.78	
13	6 474 998.11	4 897 939.90	
14	6 474 993.73	4 897 943.34	
15	6 474 978.94	4 897 951.03	
16	6 474 968.81	4 897 956.52	
17	6 474 963.82	4 897 961.64	
18	6 474 960.41	4 897 966.21	
19	6 474 946.20	4 897 984.78	
20	6 474 945.27	4 897 986.09	
21	6 474 943.71	4 897 988.75	
22	6 474 934.39	4 898 008.52	
23	6 474 931.43	4 898 014.91	
24	6 474 929.03	4 898 018.93	
25	6 474 921.27	4 898 029.68	Kraj pristupnog puta

ELEMENTI ISKOLČENJA OBJEKTA

PUMPNA STANICA DOLAC NA LAŠVI

	Koordinata		
TAČKA	Y	X	Komentar
OB1	6 474 917.46	4 898 036.93	Pumpna stanica
OB2	6 474 914.03	4 898 032.42	
OB3	6 474 910.72	4 898 034.93	
OB4	6 474 914.15	4 898 039.44	
OG1	6 474 925.59	4 898 035.37	Ograda
OG2	6 474 916.26	4 898 023.07	
OG3	6 474 904.31	4 898 032.13	
OG4	6 474 913.63	4 898 044.44	